

Section 17.24.640

DISCHARGE STRUCTURES AND OUTFLOW SITES

All details for existing and planned ponds are addressed in Appendix K, "Drainage Control Plan: Ponds, Impoundments, Diversions" and Appendix K-c, "Drainage Control, Carbone Amendment Area."

Discharge from sedimentation ponds, impoundments, and diversions will be controlled by vegetation, energy dissipators, riprap channels, and other measures, where necessary, to reduce erosion, to prevent deepening or enlargement of stream channels, and to minimize disturbance of the hydrologic balance. Discharge structures will be designed according to standard engineering-design procedures and be certified by a qualified, registered, professional engineer as meeting the performance standards of this subchapter and any design criteria specified by the department.